

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-059-24456-00-00  
Spot: SENESE Sec/Twnshp/Rge: 36-17S-20E  
1320 feet from S Section Line, 330 feet from E Section Line  
Lease Name: R B ANDERSON Well #: 6(6A)  
County: FRANKLIN Total Vertical Depth: 568 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	567		85 SX
SURF	7	20		8 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/25/2013 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, THEN PMP IN AND FILL THE PROD CSG W/CMT, PRESS UP ON SAME AND SHUT-IN. IF CAN NOT PMP FLUID, RIH W/1"TBG, PMP PROD CSG FULL OF CMT, POOH TBG, TOP PROD CSG OFF W/CMT, PRESS UP AND SHUT WELL IN. RETURN AT A LATER DATE, CUT CSG OFF BELOW "PLOW DEPTH".

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE  
Date/Time Plugging Completed: 06/25/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO TD IN 2-7/8 INCH CASING AND FILL TO SURFACE WITH PORTLAND CEMENT. PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 700 PSI. USE TOTAL OF 21 SACKS OF CEMENT.

Perfs:

RECEIVED  
OCT 30 2013  
KCC Chanute Dist. #3

LS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] 10/30/13  
(TECHNICIAN)

11/21/13

KCC WICHITA

Form CP-2/3

NOV 01 2013

RECEIVED