

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20212-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 7-33S-40W
4655 feet from S Section Line, 1972 feet from E Section Line
Lease Name: LOW E Well #: 3
County: MORTON Total Vertical Depth: 5430 feet

Operator License No.: 33136
Op Name: ANADARKO E & P ONSHORE LLC
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2582		WITH 15 SX CMT
PROD	4.5	2790	1828	WITH 700 SX CMT
SURF	8.625	1619		WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/26/2013 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2582' WITH 15 SX CMT. SHOOT 4 1/5" OFF AT 2100'. PLUG AT 2100' WITH 40 SX CMT. PLUG AT 1670' WITH 80 SX CMT. PLUG AT 550' WITH 60 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE
Date/Time Plugging Completed: 09/26/2013 2:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

SET CIBP @ 2582' WITH 15 SX CMT. 1ST PLUG AT 1878' WITH 40 SX CMT. 2ND PLUG AT 1670' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 180 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2632	2692		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

OCT 15 2013
CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 01

RECEIVED
OCT - 9 2013
KCC DODGE CITY

Signed Nathan Willis
11/19/13 (TECHNICIAN)