

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00614-00-00
Spot: SENENW Sec/Twnshp/Rge: 9-30S-8W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: EVANS C Well #: 2
County: KINGMAN Total Vertical Depth: 4327 feet

Operator License No.: 34357
Op Name: ATLAS OPERATING LLC
Address: 15603 KUYKENDAHL, STE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4325	710	100 SX
SURF	8.625	246		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2013 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: _____ Phone: _____

Proposed
Plugging
Method:

PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 10/15/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

TUBING AT 4050' SPOTTED 35 SX CEMENT WITH 200 LBS OF HULLS. PERF CASING AT 1300' RAN TUBING IN SPOTTED 35 SX OF CEMENT. PULLED CASING AT 710', RAN TUBING TO 800' SPOTTED 35 SX CEMENT, COULD NOT TAG CEMENT RAN BACK IN WITH TUBING TO 800' SPOTTED 50 SX CEMENT, TAGGED AT 730', PULLED TUBING TO 300' CIRCULATED TO SURFACE WITH 125 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4224	4236		
4202	4215		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS PLUG JOB. DENIED TA

Plugged through: TBG

District: 02

Signed

BJ Hope
10/19/13

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

OCT 22 2013

CONSERVATION DIVISION
WICHITA, KS