

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20571-00-00  
Spot: NESENE Sec/Twnshp/Rge: 34-8S-27W  
3630 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SHARON LEASE Well #: 1  
County: SHERIDAN Total Vertical Depth: 4075 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4045		125 SX
SURF	8.625	206		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2013 10:00 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.  
8 5/8" surface casing set at 206' w/140 sx cement. 4 1/2" production casing set at 4045' w/125 sx cement.  
TD 4075', PBD 4004'. Perforations: 3791' - 3793', 3832' - 3834', 3843' - 3848', 3874' - 3880', 3929' - 3931', 3970' - 3973' and 3993' - 3996'. Tubing sanded in production casing at 3150'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/01/2013 5:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Tubing cut at 3150'. Pulled tubing to surface. Perforated production casing at 2282' and 1507'. Ran tubing to 3130' and pumped 110 sx cement w/200 # hulls. Pulled tubing to 1600' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 75 sx cement w/100 # hulls. Cement to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 50 sx cement.

GPS: 39.31617 N -100.31301W Well formerly known as Mosier # 1.

Perfs:

Remarks: SOS CEMENT CO TICKET # 1116

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*  
10/19/13

(TECHNICIAN)

CM

OCT 07 2013

KCC WICHITA

Form CP-2/3

OCT 24 2013

RECEIVED