

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-203-20237-00-00  
Spot: N2NWSWNW Sec/Twnshp/Rge: 3-18S-36W  
1425 feet from N Section Line, 330 feet from W Section Line  
Lease Name: ZELLNER Well #: 1-3  
County: WICHITA Total Vertical Depth: 5070 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	267		WITH 200 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2013 12:30 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: KELLY WILSON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: IST PLUG AT 2430' WITH 50 SX CMT. 2ND PLUG AT 1470' WITH 80 SX CMT. 3RD PLUG AT 735' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE  
Date/Time Plugging Completed: 10/20/2013 2:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

IST PLUG AT 2430' WITH 50 SX CMT. 2ND PLUG AT 1470' WITH 80 SX CMT. 3RD PLUG AT 735' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Nathan Willis  
11/08/13 (TECHNICIAN)

RECEIVED  
OCT 29 2013  
KCC DODGE CITY

KCC WICHITA Form CP-2/3  
NOV 01 2013  
RECEIVED

*Handwritten mark*