

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03118-00-00
Spot: SWNENE Sec/Twnshp/Rge: 16-15S-12W
990 feet from N Section Line, 990 feet from E Section Line
Lease Name: ZEMAN Well #: 4
County: RUSSELL Total Vertical Depth: 3239 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3075		
CIBP		3110		
PROD	5.5	3055		125 SX
SURF	10	725		600 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2013 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 17 sx gel and 600 # hulls.
Perforations: 1250', 725' and 300'

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2013 6:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2947' and pumped 17 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1300' and pumped 125 sx cement w/300 # hulls. POOH. Hooked up to casing and pumped 175 sx cement. Cement circulated out braden head and filled cellar. Checked fill up on 09/18/2013. Top of cement at 14'.

GPS: 38.75223 -098.65548

Perfs:

Top	Bot	Thru	Comments
3038	3045		
3020	3030		

Remarks: QUALITY CEMENTING TICKET # 7860

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel
9/18/13

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

CM

SEP 25 2013

OCT 02 2013

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS