

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21344-00-00
Spot: SWSNWNE Sec/Twnshp/Rge: 26-6S-29W
1010 feet from N Section Line, 1870 feet from E Section Line
Lease Name: ZODROW Well #: 1-26
County: SHERIDAN Total Vertical Depth: 4530 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		170 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/07/2013 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BERNIE Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1081

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN Witness Type: NONE
Date/Time Plugging Completed: 10/07/2013 10:30 AM KCC Agent: DAVID WANN

Actual Plugging Report:

1st plug @2500 w/25 sx
2nd plug @1660 w/100 sx
3rd plug @270 w/40 sx
4th plug @40 w/10 sx


Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed  (TECHNICIAN)
10/08/13

CM

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

OCT 10 2013

OCT 21 2013

CONSERVATION DIVISION
WICHITA, KS