

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-21782-00-00  
Spot: W2SESWNE Sec/Twnshp/Rge: 6-32S-42W  
3007 feet from S Section Line, 1794 feet from E Section Line  
Lease Name: HORIZON Well #: 1-6  
County: MORTON Total Vertical Depth: 5210 feet

Operator License No.: 32638  
Op Name: NADEL AND GUSSMAN LLC  
Address: 15 E 5TH ST STE 3200  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3792		
PROD	5.5	3888	1833	WITH 370 SX CMT
SURF	8.625	1472		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/20/2013 10:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SQUEEZE PERFS WITH 30 SX CMT & 200# HULLS. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/20/2013 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 30 SX CMT TO 3730'. PRESSURE TO 500#. 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 450' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3802	3804		
3735	3739		
3728	3730		
3511	3516		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 22 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

Ken Jehlik  
10/27/13 (TECHNICIAN)

RECEIVED

OCT -7 2013

KCC DODGE CITY

Row