

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-20020-00-00  
Spot: NESENW Sec/Twnshp/Rge: 26-22S-2W  
3630 feet from S Section Line, 3700 feet from E Section Line  
Lease Name: VOGT Well #: 4  
County: HARVEY Total Vertical Depth: 3491 feet

Operator License No.: 30280  
Op Name: SUNFLOWER WELL SERVICE, INC.  
Address: 408 N 4TH PO BOX 341  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3000		
CIBP		3438		
PROD	5.5	3469		150 SX CMT
PROD	4.5	3490		225 SX
SURF	8.625	254		150 SX CMT
SURF	8.625	274		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2013 12:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: \_\_\_\_\_ Phone: (620) 654-8342

Proposed Plugging Method: As Per KCC Instructions

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/17/2013 3:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 2575' CAPPED W 4 SX CEMENT. TRIED TO PULL CASING TOP JOINT CAME LOOSE, GOT TOP JOINT SCREWED BACK ON, CUT HEAD OFF RAN ONE INCH DOWN BETWEEN SURFACE AND 4.5' CASING TO 310' STACKED OUT, PUMPED 40 SX CEMENT WITH 1 SX GEL. RAN 2 INCH TUBING INSIDE 4.5 TO 400' PUMPED 14 SX OF GEL THEN 100 SX CEMENT, LOST PRESSURE, BACKED OFF. WAITED 2.5 HOURS PUMPED ANOTHER 15 SX GOT CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3445	3451		
2939	2968		
2626	2648		

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 22 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENTING OUT OF BURRTON, 60/40 4% POS MIX, TICKET #40728

Plugged through: TBG

District: 02

Signed BJ Hope  
10/26/13 (TECHNICIAN)