

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-19165-00-02
Spot: NWENWSE Sec/Twnshp/Rge: 35-10S-21W
2342 feet from S Section Line, 1656 feet from E Section Line
Lease Name: SCHNEIDER B Well #: 2
County: GRAHAM Total Vertical Depth: 4100 feet

Operator License No.: 31826
Op Name: T & C MFG. & OPERATING, INC.
Address: 1020 HOOVER ST PO BOX 225
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
LI	4.5	3743		150 sx
PKR		3725		
PROD	5.5	3757		175 SX
SURF	8.625	210		150 SX
TI	2.875	3725		

Well Type: SWD UIC Docket No: D12777.0 Date/Time to Plug: 10/21/2013 8:30 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: MIKE DAVIS Company: ROME CORPORATION DBA WEST Phone: (620) 793-0897

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/700 # hulls.
DV at 1553'. 300 sx open hole complete.
Tubing stuck in hole at 1626'. Can not get out.
Shot perforations at 800' and 175'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/23/2013 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Screwed onto tubing and pumped 125 sx cement w/300 # hulls to 850 psi. Pulled tubing out. Ran tools in and shot perforations at 800' and 175'. Ran tubing back into 1626' and pumped 105 sx cement w/150 # hulls. Good circulation of cement. Pulled tubing. Tied on to casing and squeezed w/20 sx cement. Shut in pressure 300 psi. Tied on to back side and squeezed w/8 sx cement. Shut in pressure 400 psi.

GPS: 39.13891 -099.62939

Perfs:

Remarks: ALLIED CEMENTING TICKET # 54898 AND 54813

Plugged through: TBG

KCC WICHITA

NOV 13 2013

RECEIVED

District: 04

Signed [Signature]
cc to UIC 11/19/13 (TECHNICIAN)

CM

NOV 06 2013

11/26/13