

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26602-00-00
Spot: SWSENEW Sec/Twnshp/Rge: 5-13S-20W
1325 feet from S Section Line, 2000 feet from W Section Line
Lease Name: HENRY Well #: 1
County: ELLIS Total Vertical Depth: 3930 feet

Operator License No.: 4787

Op Name: TDI, INC.

Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		150 sx

Well Type: DH

UIC Docket No:

Date/Time to Plug: 10/24/2013 12:00 AM

Plug Co. License No.: 33350

Plug Co. Name: SOUTHWIND DRILLING, INC.

Proposal Rcvd. from: LARRY

Company: SOUTHWIND DRILLING, INC.

Phone: (620) 617-3408

Proposed Plugging Method: Ordered 270 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT BEDORE

WitnessType: NONE

Date/Time Plugging Completed: 10/24/2013 1:45 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

1st plug @3800 w/50 sx
2nd plug @1500 w/25 sx
3rd plug @720 w/100 sx
4th plug @275 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP

KCC WICHITA

NOV 07 2013

RECEIVED

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

11/26/13

OCT 25 2013