

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26595-00-00
Spot: SWNENWSW Sec/Twnshp/Rge: 7-15S-19W
1985 feet from S Section Line, 835 feet from W Section Line
Lease Name: YOUNGER Well #: 1
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 4787
Op Name: TDL, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1269		375 sx

Well Type: DH UIC Docket No: Date/Time to Plug: 11/02/2013 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: LARRY Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-3478

Proposed Plugging Method: Ordered 245 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 11/02/2013 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @3620 w/50 sx
2nd plug @1300 w/40 sx
3rd plug @500 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: SWIFT

Plugged through: DP

District: 04

Signed

Case Morris
11/06/13 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

NOV 14 2013

NOV 25 2013

RECEIVED