

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20418-00-01
Spot: S2SESE Sec/Twnshp/Rge: 31-11S-22W
330 feet from S Section Line, 660 feet from E Section Line
Lease Name: SPENA B Well #: 1
County: TREGO Total Vertical Depth: 4165 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3920		150 SX
SURF	8.625	152		110 SX
T1	2.375	3822		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2013 9:30 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: THOMAS ATKINS Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 216-0155

Proposed Shot perforations at 145', 1058', 1865' and 2400'.
Plugging Perforations at 3663', 3666', 3679', 3686', 3723', 3735', 3753' and 3758'.
Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2013 5:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3760' and pumped 50 sx cement w/80 # hulls. Pulled tubing to 3150' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1650' and pumped 300 sx cement w/150 # hulls. Ran out of cement. Pulled tubing out of hole and had to wait 2 hours on cement. Ran tubing back to 1085' and pumped 85 sx cement w/50 # hulls. Circulated cement out of 4 1/2" production casing and shut in. Pumped 50 sx cement. Circulated cement to surface. 8 5/8" surface casing full. Shut in backside. Pulled tubing out and topped off w/12 sx cement. Casing is full.

GPS: 39.04560 -099.79982

Perfs:


Top	Bot	Thru	Comments
3753	3758		
3733	3737		
3723	3735		
3722	3725		
3679	3686		
3663	3666		

Remarks: CONSOLIDATED CEMENT TICKET # 44288

Plugged through: TBG

District: 04

Signed


11/26/13 (TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

NOV 25 2013

RECEIVED

NOV 14 2013