

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-22223-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 11-21S-32W
2305 feet from S Section Line, 335 feet from W Section Line
Lease Name: JOYCE TRUST 2132 Well #: 1-11
County: FINNEY Total Vertical Depth: 5617 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3950		WITH 2 SX CMT
CIBP		4080		
CIBP		4650		
CIBP		4780		
CIBP		5385		
PROD	5.5	5617	0	WITH 525 SX CMT
SURF	8.625	1920		WITH 600 SX CMT

Well Type: SIOW UIC Docket No: _____ Date/Time to Plug: 11/15/2013 10:30 AM
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC
Proposal Rcvd. from: ANTHONY Company: TITAN WELL SERVICE, LLC Phone: (405) 828-4225

Proposed Plugging Method: CIBP @ 3950' WITH 2 SX CMT. CUT & PULL CASING. RUN TBG TO 2100'. PLUG AT 2100' WITH 25 SX CMT. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2013 9:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 3950' WITH 2 SX CMT. CIRCULATE HOLE WITH MUD. ATTEMPTED SPLIT COLLAR SHOT @ 1182' & 1050'. COULD NOT PULL 5 1/2" CASING. RAN A SECOND BOND LOG. TOC @ 950'. RAN A 3RD SPLIT COLLAR SHOT. SHOT CASING COLLAR @ 710'. PULLED CASING UP 10' & IT STUCK. PULLED TO 50000#. COULD NOT MOVE UP OR DOWN. RAN TBG TO 1500'. PLUG AT 1500' WITH 40 SX CMT. CIRCULATION UP 5 1/2". PLUG AT 710' WITH 50 SX CMT TO COVER WINDOW IN 5 1/2" CASING. CIRCULATED UP 5 1/2" CASING. PLUG AT 60' WITH 35 SX CMT TO FILL 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
5408	5412		
4884	4894		
4811	4820		
4796	4802		
4706	4710		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

KCC WICHITA
NOV 21 2013
RECEIVED

RECEIVED

District: 01

NOV 19 2013

Signed

Ken Jehlik
11/26/13
(TECHNICIAN)

KCC DODGE CITY

AM