

To: 1 040272
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C N/2 NW SE, SEC. 32, T 32 S, R 12 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-9-89
API NUMBER 15- 007-22,099-40-40
2310 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Lease Name Barthlow Well # 1

Operator: Graves Drilling Company Inc.

County Barber 153.35

Name &

Address 151 North Main, Suite 850

Well Total Depth 4780 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well ☒ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 9 Month: 5 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4778' PBTD 4770' Perfs at 4655-65'

1st plug sand back to 4600' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

5-5-89
Plugging Proposal Received by Richard Lacey

CONSERVATION DIVISION
Wichita, Kansas

(TECHNICIAN)

Plugging Operations attended by Agent? ☒ Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 9 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 5 sx cement on top of
sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 650 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by B.J. Titan. Recovered 3600' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)

DATE 5-17-89

INV. NO. 24878

Signed Stephen J. Pfeiffer
(TECHNICIAN)