

To: 1 040235
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-14
API NUMBER 15-007-21,868 ~~X~~
NE NE SW, SEC. 34, T 32 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3378

Lease Name Randels Well # 1-34

Operator: Sage Oil Company
Name &

County Barber

120.25

Address 4216 North Portland
Oklahoma City, OK 73112

Well Total Depth 3700 feet

Operator Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2:30 p.m. Day: 14 Month: 3 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-3763

were: 4 1/2" at 3700' PRTD 3648' Perfs at 3562-3590'

1st plug sand back to 3400' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 14 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back from 3648-3400' and dumped 4 sx cement on top
of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 2% gel, 2% cc by B.J. Titan. Recovered 2975' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
id, ~~XXXXXX~~ observe this plugging.

DATE 3-23-89

Signed Stephen J. Puffer
(TECHNICIAN)

INV. NO. 24208