

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6759

Operator: DUXBURY OIL COMPANY
Name & Address 90 GOLD
SAN FRANCISCO, CA 94133

API NUMBER 15-165-21,055-0000 ✓

SE/4, Sec. 21, T 19 S, R 16 W/X

1650 feet from X/S section line

2310 feet from X/E section line

Lease Name Dyer Well # 1

County Rush

Well Total Depth 3853 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 1133

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE DRILLING, INC. License Number 5722

Address 801 UNION CENTER, WICHITA, KS 67202

Company to plug at: Hour: 11:30 PM Day: 2 Month: FEB Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO WILMER DRILLING

(company name) ABERCROMBIE (phone) _____

were: to use 50/50 Pozmix, 4% gel-3% CC & spot PE plug @
3750' w/50 sz; 2nd plug @ 1170' w/70 sz; 3rd
plug @ 540' w/40 sz; 4th plug @ 40' w/solid
bridge & 8 7/8 plug & 10 sz cmt to surface. Circ. 10 sz
in rat hole.

Signed R. Bralutian
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 AM Day: 3 Month: FEB Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered.

Remarks: 8 7/8 cemented w/450 sz. Com - Anhydrite Top @
1123, base @ 1152' - Anhydrite top @ 3754

STATE CORPORATION COMMISSION
(RECEIVED)

FEB 10 1983
2-10-83

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

INVOICED

DATE 3-8-83

INV. NO. 3489-W

Signed R. Bralutian
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82