

1 010095

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,173 -0000

SW NE NE, SEC. 7, T 19 S, R 16 W/T  
4290 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

990 feet from E section line  
Hagerman-

Operator: Mustang Drilling & Exploration, Inc  
Name & Address P. O. Box 1609  
Great Bend, KS 67530

Lease Name Wilhelm Well # 1  
County Rush 125.03

Well Total Depth 3847 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1005

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 26 Month: February Year: 19 86

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3844' Perfs at 3833-37'; 3838-42'

1st plug sand back to 3780' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:40 pm Day: 26 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3780' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 25 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 170 sx cement.

Maximum pressure 600 psi and shut in 200 psi

Remarks: Recovered 3200' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (cd no 872888) observe this plugging.

DATE MAR 04 1986

RECEIVED  
STATE CORPORATION COMMISSION Signed \_\_\_\_\_

[Signature]  
(TECHNICIAN)

INV. NO. 12849

MAR 4 1986  
3-4-86  
CONSERVATION DIVISION