

2-12-88

To: 1 061063
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,283 -0000
NE NE SE, SEC. 32, T 19 S, R 16 W/EX
2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6563
Operator: Double "B" Oil, Inc.
Name & Address: 300 West Douglas, Suite 320
Wichita, KS 67202

Lease Name Rosa Well # 1
County Rush 126.75
Well Total Depth 3900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1081

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 12 Month: 2 Year: 19 88

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3899' PBD 2300' Perfs at 3763-68, 3771-4, 3776-8, 3783-5, 3796-8, 3811-13, 2158-63'
CIBPs at 2300, 3780, and 3794'

1st plug sand back to 2100' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Paul Luthi' (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:40 p.m. Day: 12 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 2100' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Maximum pressure 800 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1600' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
FEB 17 1988
2-17-88
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(10/10/88) observe this plugging.

DATE 2-18-88

Signed Paul A. Luthi' (TECHNICIAN)

INV. NO. 19891