

15-077-20033-0000  
4-23

2-040877

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15- 9-12-67

C-SE-SW, SECTION 7 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 06568 660 FEET FROM S SECTION LINE  
OPERATOR Kaiser-Francis Oil Co. 3300 FEET FROM E SECTION LINE  
NAME & P.O.Box 21468  
ADDRESS Tulsa, OK. 74121  
LEASE NAME: Wingate #4  
COUNTY: Harper 143.75  
WELL TOTAL DEPTH: 4423  
PIPE: 4 1/2 4405  
SURFACE CASING: 8 5/8 222

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Mikes Testing & Salvage

ADDRESS: Chase Ks. LICENSE: 31529

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Mikes Testing & Salvage PHONE: \_\_\_\_\_

WERE: Sand to 4350 & 4 sks Cement  
35 sks cmt 1425  
35 sks cmt 950  
Circulate cmt from 275-0

PLUGGING PROPOSAL RECEIVED BY: Mike Wilson


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART (  ) NONE ( )

COMPLETED: HOUR: 1200 DAY: 23 MONTH: 4 YEAR: 1997

ACTUAL PLUGGING REPORT: The Perfs were covered with sand from 4405 to 4315, and capped with 4 sks of cement. The 4 1/2 was recovered from 2208 and pulled to 1425 where 35 sks of cement was spotted in place. 4 1/2 pulled to 950 where 35 sks cement was spotted in place. the 4 1/2 was pulled to 275 where the hole was circulated to surface. Remaining 4 1/2 pulled and the cement was brought back to surface.

REMARKS: Allied Cementing 60/40 4% gel

INVOICED RECEIVED  
KANSAS CORPORATION COMMISSION  
DATE 4-28-97 APR 25 1997  
INV. NO. 48020 4-25-97  
CONSERVATION DIVISION  
WICHITA, KS

I DID OBSERVE THIS PLUGGING.  
  
STEVE VANGIESON