

4-17
K-077-10067-0000

2- 040878

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15 12-20-54

SW-NW-NW, SECTION 7 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 06568 4290 FEET FROM S SECTION LINE
OPERATOR Kaiser-Francis Oil Co. 4950 FEET FROM E SECTION LINE
NAME & ADDRESS P.O.Box 21468
Tulsa, OK. 74121
LEASE NAME: Grabbs B #1
COUNTY: Harper 146.74
WELL TOTAL DEPTH: 4515
PIPE: 5 1/2 @ 4501
SURFACE CASING: 8 5/8 @ 168

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Mikes Testing and Salvage
ADDRESS: Chase Ks. LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Mikes Testing & Salvage PHONE: _____

WERE: Sand to 4360 & 4 sks cmt
35 sks @ 1400
35 sks @ 900
Cir. Cmt from 250-0

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1530 DAY: 17 MONTH: 4 YEAR: 1997

ACTUAL PLUGGING REPORT: The Perfs were covered with sand from the the PBD of 4482 to 4300 and capped with 5 sks of cmt. The 5 1/2 was recovered from 2400, and pulled to 1411, where 35 sks of cmt was spotted. The 5 1/2 was pulled to 908, where 35 sks of cmt was spotted. The 5 1/2 was pulled to 248 where cmt. was circ to surface. Remaining 5 1/2 was pulled and cmt. topped off.

REMARKS: Allied Cement 60/40 4% gel

INVOICED

RECEIVED
KANSAS CORPORATION COMMISSION

DATE 4-28-97
INV. NO. 48021

APR 25 1997
4-25-97
CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.
[Signature]
STEVE VANGIESON