

15-077-19011-0000  
2-12

2-040611

251  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 5-25-64

C NE NW, SECTION 7 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 6568

4620 FEET FROM S SECTION LINE  
3300 FEET FROM E SECTION LINE

OPERATOR Kaiser-Francis Oil Co.  
NAME & P. O. Box 21468  
ADDRESS Tulsa, OK 74121

LEASE NAME: Grabb #B-2

COUNTY: Harper 146.25

WELL TOTAL DEPTH: 4500' PB 4450'

CONDUCTOR PIPE: " @ "

SURFACE CASING: 8-5/8" @ 216'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Bill Fulls  
COMPANY NAME: Kelso Casing PHONE: \_\_\_\_\_

WERE: PBTD 4450' - 4-1/2" @ 4499' - perfs 4430-40' - CIBP  
4450' - perfs 4468-78' - sand to 4380' & 4 sx - 35 sx @  
1450' - 35 sx @ 1000' - circ 265'

PLUGGING PROPOSAL RECEIVED BY: Glenn Ward

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 11:00 DAY: 12 MONTH: 2 YEAR: 1991

ACTUAL PLUGGING REPORT:

The perfs were sanded to 4380' & capped w/4 sx cmt -  
4-1/2" recovered from 3200 and pulled to 1481' where  
35 sx cmt spotted - pipe pulled to 1006' and 35 sx cmt  
spotted - 4-1/2" pulled to 287' and cmt circ to surf.

REMARKS: B. J. Services #636442 40/60 4%

I DID OBSERVE THIS PLUGGING OPERATION

INVOICED

2-26-91

DATE MAR 05 1991 FEB 26 1991

Steve Van Gieson  
Steve Van Gieson (AGENT)

INV. NO. 30998  
CONSERVATION DIVISION  
Wichita, Kansas