

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00846-00-01
Spot: SWNWNW Sec/Twnshp/Rge: 17-31S-8W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: C E WARREN Well Number: 1
County: HARPER Total Vertical Depth: 4423 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 78020
WICHITA, KS 67278

Conductor Pipe: Size feet: 143.75
Surface Casing: Size 8.625 feet: 227 525 SX CMT
Production: Size 5.5 feet: 4423
Liner: Size feet:

Well Type: SWD UIC Docket No: D06653.0 Date/Time to Plug: 11/30/2001 1:15 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone:

Proposed Plugging Method: Perfs @ 3938'-3999', Sand to 3751' and 5sxs, 35sxs-1300', 35sxs-700'. Circulate from 310'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 11/30/2001 1:15 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were covered w/sand to 3751' and capped w/5sxs of sand. A CIBP was set at 2700' which was above the bad casing. The casing was recovered from 1472' and pulled from the wellbore. Tubing was run in the well to 1300', where 35sxs of cement was spotted. The tubing was pulled to 700', where 35sxs of cement was spotted. The tubing was pulled to 310', where cement was circulated. The remaining tubing was pulled and the cement was topped off.

RECEIVED
KCC DISTRICT #2

DEC 07 2001


WICHITA, KS

Remarks: ACID SERVICES 60/40 4% GEL #1315

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-10-01

INV. NO. 2002061045