

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-001-21,405-00-00

SE/4, Sec. 10, T 32 S, R 12 W/4

NE-SW-SE/4 feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Lease Name MELVIN Well # 1

Operator: GRAVES DRILLING Co., Inc
Name & Address 910 Union Center
Wichita, KS 67202

County BARBER

Well Total Depth 4370 feet \$ 142.03

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 442

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30pm Day: 7 Month: April Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Elmo Morgenstern

(company name) Clarke (phone) _____

were: Sand bottom to 4275 + 4 1/2 cmt. Rec. pipe
and pump 50/50 Poz mix, 2% gel - 4% CaCl in the
following sequence: 2 1/2 cmt; 20 1/2 gel;
70 1/2 cmt; then 10 1/2 gel, 1 1/2 cmt, 8 5/8 plug
and finish w/ 115 1/2 cmt.

Signed R Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:30pm Day: 7 Month: April Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered. Maximum
pump pressure @ 700#; Shut in pressure
@ 600#. Cementing by Allied.

Remarks: Elev. 1496 GL - Anhydrite top 467
4 1/2 @ 4367 w/ 100 1/2 cmt; rec. 3340' Perf @ 4303-15
8 5/8 set w/ 285 1/2 cmt

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above plugging instructions were given as herein stated
and that I ~~did~~ (did not) observe this plugging.

APR 12 1983
CONSERVATION DIVISION
Wichita, Kansas

Signed R Barluttan
(TECHNICIAN)

INVOICED

DATE 4-19-83

INV. NO. 4056-W

FORM CP-2/3
Rev. 9-82