

1060287

-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,544X

SE/4 NE/4, SEC. 7, T. 32 S, R. 12 E
N SE Corner of
3300 feet from ~~XXX~~ section line
W SE Corner of
660 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5993

Lease Name Aubley Well # 1

Operator: KBW Oil & Gas Company

County Barber

Name & Address 3632 N.W. 51st, Suite 205

Well Total Depth 4303 150.61 feet

Oklahoma City, OK 73112

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 304 304

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 am Day: 27 Month: July Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" set at 4301' Perfs 4238

1st plug sand back to 4200' and dump 4 sx cement on top of sand through bailer

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, and 125 sx cement

RECEIVED
STATE CORPORATION COMMISSION

AUG 01 1984

Plugging Proposal Received by Paul A. Luthis (TECHNICIAN)

CONSERVATION DIVISION Operations attended by Agent?: All Part _____ None _____
Wichita, Kansas

Operations Completed: Hour: 12:15 pm Day: 27 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4301' Perfs 4238'

1st plug sanded back to 4200' and dumped 4 sx cement on top of sand through bailer, 2nd

plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel and 125 sx cement.

Maximum pressure 850# and shut in pressure 650#

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun. They recovered 3650' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-9-84

Signed Paul A. Luthis (TECHNICIAN)

INV. NO. 2919