

10-8-87

To: 1 120027
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,167-00-00

Approx. SE NW SE SEC. 7, T. 32 S, R. 12 W/EX

1650 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020

Lease Name Orr Well # 1-7

Operator: Rine Exploration Company

County Barber

Name & Address 300 West Douglas, Suite 645

144.30

Well Total Depth 4440 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 205 East Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 3 p.m. Day: 8 Month: 10 Year: 19 87

Plugging proposal received from John Armbruster

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1564' Anhydrite 600'

1st plug at 660' with 50 sx cement,

2nd plug at 390' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6 p.m. Day: 8 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 660' with 50 sx cement,

2nd plug at 390' with 40 sx cement,

3rd plug at 50-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

OCT 13 1987

10-13-87

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-14-87

Signed [Signature] (TECHNICIAN)

INV. NO. 18499