

To: 1 040376
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-8
API NUMBER 15- 007-20,544-00-00

E/2 W/2 NE, SEC. 5, T 32 S, R 12 W XX

3960 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Clarke "E" Well # 1

Operator: TXO Production Corporation

County Barber 139.26

Name: TXO Production Corporation

Well Total Depth 4285 feet

Address 1660 Lincoln Street, Suite 1800

Conductor Pipe: Size _____ feet

Denver, CO 80264

Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1:45 p.m. Day: 8 Month: 12 Year: 19 89

Plugging proposal received from Bryan Woods

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4284' PBDT 4235' Perfs at 4205-20, 4188-93'

1st plug sand back to 4130' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 8 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4130' and dumped 4 sx cement on top of

sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 550 psi.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by B.J. Titan. Recoverey 3450' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 14 1989

INV. NO. 26812
12-8

Signed Stephen J. Puffer
(TECHNICIAN)