

1 040005

11-10-87

API NUMBER 15-007-20,709-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2 NE SE, SEC. 5, T 32 S, R 12 (W)X
2310 feet from S section line

TECHNICIAN'S PLUGGING REPORT

660 feet from E section line

Operator License # 5171

Lease Name Clark "G" Well # 1

Operator: TXO Production Corporation
Name & Address 155 North Market, Suite 100
Wichita, KS 67202

County Barber 138.78
Well Total Depth 4270 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 10 Month: 11 Year: 19 87

Plugging proposal received from Allen Dick

(company name) TXO Production Corporation (phone) 316-886-5606

were: 2 7/8" at 4268' PRTD 4228' Perfs at 4190-4214' Elevation 1479'GL

1st plug pump 1 sx hulls and 25 sx cement to bottom,

2nd plug perforate at 320', pump 25 sx cement down 2 7/8",

3rd plug pump 65 sx cement down 8 5/8".

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 10 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped bottom with 2/3 sx hulls and 10 sx cement -
pressured to 500 psi,

2nd plug perforated at 320' with dynamite charge, started pumping cement down 2 7/8"
casing with 25 sx cement. Pumping pressure 100 psi, shut in 100 psi,

3rd plug pumped down annulus with 4 1/3 sx hulls and 65 sx cement. Pumping pressure
200-700 psi and shut in 500 psi.

STATE CORPORATION COMMISSION
11-18-87

Remarks: Used 60/40 Pozmix 6% gel by B.I. Titan. No casing recovery.
(If additional description is necessary, use BACK of this form.)

NOV 18 1987

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 12-3-87

INV. NO. 19071

observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)