

1040006

11-12-87

API NUMBER 15- 007-20,746-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE SW, SEC. 5, T 32 S, R 12 (W) EX
1910 feet from S section line
3170 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corporation
Name & Address: 155 North Market, Suite 1000
Wichita, KS 67202

Lease Name Turnbull Well # 1
County Barber 139.46
Well Total Depth 4291 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Great Bend Casing Pullers Inc. License Number 4635
Address: P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 12 Month: 11 Year: 19 87

Plugging proposal received from Alan Dick

(company name) TXO Production Corporation (phone) 316-886-5606

were: 2 7/8" at 4290' PBSD 4232' Perfs at 4214-34' Elevation 1490' GL

1st plug pump 200 lbs. hulls and 10 sx cement,

2nd plug shoot tubing at 600' and pump 30 sx cement,

3rd plug pump down annulus 500 lbs. hulls and 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 12 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped down 2 7/8" casing with 100 lbs. hulls and 10

sx cement. Pressured to 1000 psi. Used 60/40 Pozmix 6% gel,

2nd plug perforate at 600' with dynamite charge, pumped down 2 7/8" casing with 30 sx

cement. Pumping pressure 150-200 psi and shut in 200 psi.

3rd plug pumped down annulus with 500 lbs. hulls and 150 sx cement. Pumping pressure

200-800 psi and shut in 625 psi. Used 60/40 Pozmix 6% gel 2% cc for 2nd & 3rd plugs.

Remarks: Used 60/40 Pozmix 6% gel & 6% gel 2% cc by B.J. Titan. No casing recovery. STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

NOV 18 1987 11-18-87

INVOICED

DATE 12-3-87

INV. NO. 19072

Signed Stephen J. Pfeiffer (TECHNICIAN)