

1 040541

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,559-00-00

SE NE NE, SEC. 20, T. 30 S, R. 15 W/E

4290 feet from S section line

330 feet from E section line

Lease Name Gibson Well # 2-C

County Barber 152.75

Well Total Depth 4700 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 978

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:45 p.m. Day: 28 Month: 5 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4699' w/200 sx cement, Perfs at 4526-36'

1st plug sand back to 50' above perfs and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m Day: 28 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4470' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement,

Maximum pressure 1100 psi and shut in 550 psi.

RECEIVED STATE CORPORATION COMMISSION

JUN 07 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION WICHITA, KANSAS

INVOICED

(if necessary) observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 6-17-91

INV. NO. 32161