

1 040542

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,367-00-00
C SW NE, SEC. 20, T 30 S, R 15 W&E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8405
Operator: Kingsbury Petro Corp.
Name & Address: P.O. Box 780093
Wichita, KS 67278

Lease Name Gibson Well # 1
County Barber 156.13
Well Total Depth 4804 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1003

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 28 Month: 5 Year: 19 91

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4697' w/225 sx cement, PBD 4620', Perfs at 4494-97'
1st plug sand back 50' above perfs and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1 p.m. Day: 28 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4440' and dumped 5 sx cement on top of
sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement
Maximum pressure 1000 psi and shut in 650 psi.

Remarks: Used 60/40 Pozmix .6% gel by Allied. Recovered 1800' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

INVOICED
DATE 6-17-91
INV. NO. 32160

Signed Stephen J. Pluffer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
JUN 07 1991