

6-15-88

171 R

1 040124

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,521-00-00
150' W of
C. SE. NE, SEC. 20, T. 30 S., R. 15 W. E
3300 feet from S section line
810 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Gibson Well # 2

Operator: W.L. Kirkman, Inc.

County Barber 148.20

Name & Address P.O. Box 782290

Well Total Depth 4560 feet

Wichita, KS 67218-2290

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 15 Month: 6 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4559' Perfs at 4415-19' Elevation 1766' GL

1st plug pump 1 sx hulls and 20 sx cement to 4300'

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 15 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" with 100 lbs hulls and 20 sx common cement. Stopped plug at 4390'.

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3618' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
JUN 23 1988
6-22-88

CONSERVATION DIVISION
WICHITA, KANSAS

INVOLVED

(If applicable) observe this plugging.

DATE 7-13-88

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 21325