

To: 1 040591
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 11-25 15-007-21,520-0000 197R
C. SW. NE, SEC. 4, T. 30 S, R. 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5298

Operator: Gould Oil Inc.
Name & Address 110 N. Market, Suite 411
Wichita, KS 67202

3300 feet from S section line

1980 feet from E section line

Lease Name Lee Well # B-1

County Barber 159.25

Well Total Depth 4900 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS

Company to plug at: Hour: 11:30 a.m. Day: 25 Month: 11 Year: 19 91

Plugging proposal received from Fred Mease

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 4398' w/200 sx cement, PBTD 4874', Perfs at 4660-64'

1st plug sand back to 4610' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 25 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and pumped 5 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10

sx gel, 100 lbs. hulls, and 100 sx cement.

Maximum pressure 1000 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1991

11-27-91

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1972' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOLVED

DATE 12-9-91

INV. NO. 34037

Signed Stephen J. Giffin
(TECHNICIAN)