

1050457

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,982-00-00 **R**
SW SE SE, SEC. 16, T 30 S, R 15 **W**
330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7044

Lease Name Freeman Well # 1-16

Operator: Sabine Corporation
Name & Address: 6401 NW Grand Blvd, Suite 500
Oklahoma City, OK 73116

County Barber 148.85

Well Total Depth 4580 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 978 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Co. License Number 5657

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 21 Month: February Year: 19 85

Plugging proposal received from Glen Conway

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1020' with 40 sx cement

2nd plug at 600' with 30 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:00 am Day: 21 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1020' with 40 sx cement, 2nd plug at 600' with 30 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1985 2-25-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pzomix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

(If not) observe this plugging.

INVOICED
DATE 2-27-85
INV. NO. 7177
2-21

Signed Richard W. Lacey
(TECHNICIAN)