

1060211

TO: STATE CORPORATION COMMISSION

API NUMBER 15-007-22,618-00-00  
130'S W/2 SW SE SEC. 9, T 30 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 530 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LEE "T" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER

153.53

OPERATOR LICENSE # 5123

WELL TOTAL DEPTH 4724 FEET

7/19

OPERATOR: PICKRELL DRILLING COMPANY PRODUCTION CSG: SIZE     @     ' WITH     SX

NAME AND 100 S MAIN, SUITE 505 SURFACE CASING: SIZE 8 5/8" @ 376 ' WITH     SX

ADDRESS WICHITA, KS 67202 CONDUCTOR CSG: SIZE     " @     '    

ABANDONED OIL WELL     GAS WELL     INPUT WELL     SWD WELL     D/A X

OTHER WELL AS HEREINAFTER INDICATED    

PLUGGING CONTRACTOR PICKRELL DRILLING CO., INC LICENSE NUMBER 5123

ADDRESS 100 S MAIN, SUITE 505 WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 1:30 AM DAY: 19 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KERNS

(COMPANY NAME) PICKRELL DRILLING (PHONE) 316-262-8427

WERE:    

1ST PLUG AT 750' WITH 40 SX CEMENT. 2ND PLUG AT 400' WITH 50 SX CEMENT. 3RD PLUG AT 40'  
WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 5TH PLUG TO  
CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL     PART     NONE X

OPERATIONS COMPLETED: HOUR: 4:30 AM DAY: 19 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 750' WITH 40 SX CEMENT. 2ND PLUG AT 400' WITH 50 SX CEMENT. 3RD PLUG AT 40'  
WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 5TH PLUG TO  
CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 31 2000

REMARKS: USED 60/40 POZMIX 6% GEL 1/4 FLO SEAL BY ALLIED. CONSERVATION DIVISION  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) Wichita, Kansas

I (DID NOT) OBSERVE THIS PLUGGING.

INVOICED

SIGNED

Michael Maier  
(TECHNICIAN)

DATE

8/3/00

FORM CP-2/3

INV. NO.

1060303

MB