

1 040407
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: Berexco, Inc.
Name & Address Box 123
Hays, Ks. 67601

3-16 169P
API NUMBER 15-007-21,714-00-00
SESESE, SEC. 5, T 30 S, R 15 W
330 feet from S section line
330 feet from E section line
Lease Name Judith Well # 1
County Barber 153.08
Well Total Depth 4710 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 348'

Abandoned Oil Well Gas Well Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corp. License Number 5105
Address 107 W. Fowler, Box 187, Medicine Lodge, KS. 67104
Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 3 Year: 1990

Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corp. (phone) 316-886-5665

were: 5 1/2" at 4709' - PBD-4660 - Perfs. at 4594'-4598'
1st plug - Pumped 30sx. common cement w/ 2^{cc} Thru tbg.
2nd plug - Pump 300# hulls, 10sx gel, 50sx cement, 10sx gel, 100# hulls,
release 8 5/8" wiper plug and pump 120sx. cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:30 a.m. Day: 16 Month: 3 Year: 1990

ACTUAL PLUGGING REPORT 1st plug - pumped 50sx. of common cement w/ 2^{cc}
thru 2 3/8" tbg.
2nd plug - pumped 300# hulls, 10sx gel, 50sx cement, 10sx gel, 100#
hulls, released 8 5/8" wiper plug and pumped 120sx. cement.

Maximum Pressure = 600[#] and Shut in = 300[#]

Remarks: used 60/40 poz mix 6^{cc} gel by B.J. Services. Recovered 2700' of 5 1/2"
(if additional description is necessary, use BACK of this form.) casing

INVOICED

DATE 4-5-90

WV. NO. 27771
3-16

Signed Stephen J. Pfeifer
(TECHNICIAN)