

1041307

S-28

API NUMBER 15-007-22299

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15' S. of C.S.E. NE, SEC. 6, T 30 S, R 15 W/4

3285' feet from S section line

660' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 18061

Lease Name Lee Trust Well 12

Operator: Oil Producers, Inc. of Kansas

County Barber

Name: P.O. Box 8647

Well Total Depth 4950 160.88' feet

Address: Wichita, KS. 67208-8674

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 246'

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor D.S. + W. Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS. 67525

Company to plug at: Hour: 10:30 AM Day: 28 Month: 5 Year: 1998

Plugging proposal received from Kent Strube

(company name) D.S. + W. Well Servicing, Inc. (phone) 316-587-3361

zone: 5 1/2" @ 4893' w/ 150 sx. cmt, PBD @ 4765', Perfs @ 4690'-4695' + 4742'-4748'

1st plug sand back to 4640' + dump 5 sx. cement on top of sand through bailer,

2nd plug pump down 8 5/8" surface pipe w/ 300# hulls, 10 sx. gel, 50 sx. cmt., 10 sx. gel,

100# hulls, 8 5/8" wiper plug + 125 sx. cmt.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 AM Day: 28 Month: 5 Year: 1998

ACTUAL PLUGGING REPORT 1st plug sanded back to 4640' + dumped 5 sx. of cmt. on top

of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe w/ 300# hulls, 10 sx. gel, 50 sx. cmt.,

10 sx. gel, 100# hulls, 8 5/8" wiper plug + 125 sx. cmt.

max. Pressure = 1600#, Shut in Pressure = 600#

RECEIVED KANSAS CORPORATION COMMISSION

JUN 03 1998

RECOVERED 1450' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

DATE 6-8-98 observe this plugging.

WEL NO. 50688

Signed Stephen J. Pfeifer (TECHNICIAN)

CONSERVATION DIVISION WICHITA, KS

