

1 080338

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,956-00-00

SW SE NW, SEC. 2, T 32 S, R 12 W/R

2970 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Lease Name Dawson Gress Well # 1

Operator: Graves Drilling Co., Inc.  
Name & Address: 910 Union Center  
Wichita, KS 67202

County Barber 140.56

Well Total Depth 4325 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 392

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:00 am Day: 7 Month: March Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" set at 4299' PBTB 4299' Perfs at 4257

1st plug sand back to 4200' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 8 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00 pm Day: 7 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement,

8 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

MAR 15 1985

3-15-85

CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 850 psi and shut in 550 psi

Remarks: Recovered 3720' 4 1/2" casing. Used Class H cement by Sun.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 3-18-85

Signed J.A. [Signature] (TECHNICIAN) Snd

INV. NO. 7341