

1 080519

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,674-00-00

W/2 NE NE, SEC. 2, T 32 S, R 12 W E X

4620 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5105

Lease Name Strack Well # 1

Operator: Clark Corporation for

County Barber 142.68

Name: Tim Strack

Well Total Depth 4390 feet

Address: 307 W. Kansas Avenue

Conductor Pipe: Size feet

Medicine Lodge, KS 67104

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well x Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 am Day: 2 Month: May Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" at 4326' PBTID 4360' Perfs at 4328-4338'

1st plug sand back to 4275' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 am Day: 2 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 100 sx cement.

Maximum pressure 900 psi and shut in 700 psi

Remarks: Recovered 3210' 5 1/2" casing. Used 60/40 Pozmix by BJ-Titan

(If additional description is necessary, use BACK of this form.)

INVOICED

MAY 12 1986

DATE

INV. NO. 1378

Signed

(TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

MAY 12 1986

CONSERVATION DIVISION Wichita, Kansas