

No: 1 040693
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,992-00-01
50' S of
W/2 NE SW, SEC. 10, T. 30 S, R. 15 W/E
1930 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030
Operator: Vess Oil Corporation
Name & Address: 8100 E. 22nd St. N. Bldg. 300
Wichita, KS 67226

Lease Name Bricky Well # 1
County Barber 136.82
Well Total Depth 4210 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1043

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address: P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 11 a.m. Day: 28 Month: 8 Year: 19 92

Plugging proposal received from Manny Boatwright
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4160' w/100 sx cement, Perfs at 4043-49',
1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 28 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3990' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 900 psi and shut in 350 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" casing. SEP 2 1992

(If additional description is necessary, use BACK of this form.)
observe this plugging.

INVOICED
DATE 9-14-92
INV. NO. 36147

Signed Stephen J. Puffer
(TECHNICIAN)