

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER

15-007-21,698 15-007-21698-0000

~~11-12-83~~

(of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Molz Oil Company OPERATORS LICENSE NO. 6006 6-92

ADDRESS RR 2, Box 34, Kiowa, KS 67070 PHONE # (316) 296-4558

LEASE (FARM) Ricke #1 Barber WELL NO. 1 WELL LOCATION C-SE-SE COUNTY Barber

SEC. 2 TWP. 32S RGE. 11W (E) or (W) TOTAL DEPTH 3780 PLUG BACK TO 3780

Check One:

OIL WELL        GAS WELL X D & A        SWD or INJ WELL        DOCKET NO.       

SURFACE CASING SIZE 8 5/8 SET AT 376 CEMENTED WITH 225 SACKS

CASING SIZE 4 1/2 SET AT 3767 CEMENTED WITH 125 SACKS

PERFORATED AT open hole

CONDITION OF WELL: GOOD X POOR        CASING LEAK        JUNK IN HOLE       

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand from 3780 to 3610 - 4sx cement

with dump bailer to top side - 3 hull, 10 gell, 50 cement, 10 gell, 1 hull, plug

100 sx cement - 60-40 POZ, 6% gell.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED?       

(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1-24-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ron Molz PHONE # (316) 825-4338

ADDRESS Kiowa, KS

PLUGGING CONTRACTOR Clarke Coporation LICENSE NO. 5105 6-92

ADDRESS P.O. Box 187, Medicine Lodge, KS 67104 PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Edna M. Molz

(Operator or Agent)

DATE: 1-22-92

15-007-21698-0000

**GEARHART****WELL LOG**  
DUAL INDUCTION  
LATEROLOG

TOPS MARKED

FILING NO.		COMPANY <u>DUNNE-GARDNER PETROLEUM</u>	
7569-603		WELL <u>RICKE No. 1-A</u>	
		FIELD <u>WILDCAT</u>	
		COUNTY <u>BARBER</u>	STATE <u>KANSAS</u>
LOCATION: <u>C-SE-SE</u>		STATE <u>CLASSIFIED</u>	
SEC <u>2</u> TWP <u>32S</u> RGE <u>17W</u>		JAN 23 1952 1-23-52 WEL CONSERVATION DIVISION Kansas	
Permanent Datum <u>GROUND LEVEL</u>		Elev. <u>1551</u>	
Log Measured from <u>KELLY BUSHING</u>		9 Ft. Above Perm. Datum	
Drilling Measured from <u>KELLY BUSHING</u>		Elev.: K.B. <u>1560</u> D.F. <u>—</u> G.L. <u>1551</u>	
Date	<u>11-12-83</u>		
Run No.	<u>ONE</u>		
Depth-Driller	<u>3780</u>		
Depth-Logger	<u>3781</u>		
Bottom Logged Interval	<u>3778</u>		
Top Logged Interval	<u>373</u>		
Casing-Driller	<u>85/8 @ 381</u>		
Casing-Logger	<u>373</u>		
Bit Size	<u>77/8</u>		
Type Fluid in Hole	<u>CHEM GEL</u>		
Density	Viscosity	<u>9.1 52</u>	
ph	Fluid Loss	<u>11.0 18 cc</u>	
Source of Sample	<u>FLOWLINE</u>		
Rm @ Meas. Temp.	<u>.42 @ 65 °F</u>		
Rmf @ Meas. Temp.	<u>.31 @ 64 °F</u>		
Rmc @ Meas. Temp.	<u>— @ — °F</u>		
Source of Rmf	Rmc	<u>MEAS —</u>	
Rm @ BHT	<u>.24 @ 112 °F</u>		
Time	End Circulation	<u>1030</u>	
	Logger on bottom	<u>1600</u>	
Max. Rec. Temp. Deg. F.	<u>112 °F</u>		
Equip. No.	Location	<u>7569 ENID</u>	
Recorded By	<u>BADSTEBNER</u>		
Witnessed By	<u>MR. MC GINNESS</u>		

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

January 23, 1992

Molz Oil Company  
R R 2 Box 34  
Kiowa KS 67070

Ricke 1 Barber 1  
API 15-007-21,698  
C SE SE  
Sec. 02-32-11W  
Barber County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director

200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760