

Handwritten signature/initials

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION 2E-SW-7E

SEC. 5 TWP. 32 RGE. 11W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease H.W. Skinner

Operator H.W. Skinner Address Medicine Lodge - Kansas

Field _____ County Barber

Total Depth 4406 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 182 ft - Circulated with Cement
5/8 casing set at 4339 ft - Filled back from bottom
to 4325 ft & dumped 16 sacks Cement in the 5/8 casing
Pulled 5/8 casing - Filled with mud to 182 ft -
Bridge & 20 sacks of cement - Mud to 25 ft Bridge
& 15 sacks of Cement
Bill Morgan - Plugging Contractor -

C. R. Stouck ^{MAY} 5-3-48
District Conservation Agent

Date 4-28-48

PLUGGING
FILE SEC 5 T 32 R 11W
BOOK PAGE 25 OF 33