

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 9 1964
12-9-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management Inc.Complete Address: 1515 Wichita Plaza, Wichita, KansasLease Name Ketner Well No. # 2Location SW NE SE Sec. 9 Twp. 31 Rge. 13 (E) (W) WCounty Barber Total Depth 4598Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Ace Pipe Pulling CompanyAddress: Box 304, Great Bend, Kansas License No. 2Operation Completed: Hour 1:00PM Day 8th Month Dec. Year 1964

The Above well was plugged as follows:

242' of 8 5/8" surface pipe, cement circulated. 4590' of 4 1/2" long string,
cemented with 225 sacks. Plug back to 4310'. Top perforation 4022'. Bot-
tom of the hole was sanded to 4000', and cemented with 4 sacks. Fluid
in the hole was bailed down to 240'. Bridge plug was set on fluid at 240',
and 10' of rock bridge, and cemented with 25 sacks. Hole was filled with
mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the
base of the cellar.

3600' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/9/64
INV. NO. 310-W

Signed: Archie Elving
Well Plugging Supervisor