

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTRECEIVED  
STATE CORPORATION COMMISSION  
APR 5 1965  
CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasOperator's Full Name Petroleum Management Inc.Complete Address: 1515 Wichita Plaza, Wichita, KansasLease Name Ketner Well No. # 1Location NE NE SE Sec. 9 Twp. 31 Rge. 13 (E) (W)County Barber Total Depth 4710'Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A Other well as hereafter indicated: Plugging Contractor: Ace Pipe Pulling CompanyAddress: Box 304, Great Bend, Kansas License No. 2Operation Completed: Hour 2:00PM Day 2nd Month April Year 1965

The Above well was plugged as follows:

217' of 8 5/8" surface pipe, cement circulated. 4553' of 5 1/2" long  
string, cemented with the top at 2600'. Plug back to 4233'. Top per-  
feration 4228'. Bottom of the hole was sanded to 4210', and cemented  
with 5 sacks. 2100' of 5 1/2" long string was recovered from the hole.  
Fluid in the hole was bailed down to 220'. Bridge plug set on fluid  
at 220', and 10' of rock bridge, and cemented with 25 sacks. Hole  
was filled with mud to 40', and 10' of rock bridge, and cemented with  
10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging SupervisorDATE 4/5/65INV. NO. 931-W