

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 2 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Management Inc.

Complete Address: 1515 Wichita Plaza, Wichita, Kansas

Lease Name Maddix Well No. # 1

Location SW NW SW Sec. 10 Twp. 31 Rge. 13 (E) (W)W

County Barber Total Depth 4327'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 10:00AM Day 31st Month March Year 1965

The Above well was plugged as follows:

278' of 8 5/8" surface pipe, cement circulated. 4325' of 4 1/2" long
string, cemented with 75 sacks. Plug back to 4310'. Top perferation
4260'. Bottom of the hole was sanded to 4250', and cemented with 5
sacks. 3900' of 4 1/2" long string was recovered from the hole. Fluid
in the hole was bailed down to 270', bridge plug was set on fluid at
270', and 10' of rock bridge, and cemented with 25 sacks. Hole was
filled with mud to 40', and 10' of rock bridge, and cemented with 10
sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/2/65
INV. NO. 922-10

Signed: Archie Elving
Well Plugging Supervisor