

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1963

CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Continental Oil Co.Complete Address: Box 30, Lyons, KansasLease Name A. Smith Well No. # 1Location C SE SE SW Sec. 13 Twp. 31 Rge. 13 (E) WCounty Barber Total Depth 4670Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A 

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling Co.Address: Box 221, Great Bend, Kansas License No. 49Operation Completed: Hour 12:00PM Day 27th Month June Year 1963

The Above well was plugged as follows:

260' of 13 3/8" surface pipe, cement circulated with 275 sacks.4303' of 5 1/2" long string, cemented with 350 sacks. Plugged back to4274'. Top perferation 3569'. Plug pushed to 3550', sanded and cementedwith 5 sacks. Plug was set at 265', 10' rock bridge, cemented with 35sacks. Hole was filled with mud to 40', 10' rock bridge, cemented with20 sacks to base cellar.2430' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 7/1/63  
INV. NO. 7333-WSigned: Archie Elving

Well Plugging Supervisor