

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -007-20465-00-00 (of this well)

Operator's Full Name National Oil Co.

Complete Address 200 West Douglas, Suite 550, Wichita, Ks. 67202

Lease Name Ketner Well No. 1

Location C NW SW Sec. 4 Twp 31s Rge. 13 (E) (W) X

County Barber Total Depth 4780

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12:30 Pm Day 30 Month 3 Year 1979

The above well was plugged as follows:

246' 8 5/8" casing w/225 sax cement. 4 1/2" casing set at 2995' w/125
sax cement. Plug back to 2951'-Top pref., at 2775'-Sand back to 2700'
Top sand w/ 4 sax mixed cement w/ dump bailer. Pull 2410'-4 1/2" csng.
Allied mixed & pumped 5 sax hulls-20 sax gel-release plug-mix & pumped
100 sax 50/50 posmix cement w/ 2% gel & 3%cc to top of casing. Shut
in w/300# pressure.

I hereby certify well was plugged as herein stated.

STATE CORPORATION COMMISSION

Signed: Bill Owen @
Well Plugging Supervisor

INVOICED APR 3 1979
DATE 4-5-79
CONSERVATION DIVISION
Wichita, Kansas
INV. NO. 9359-u