

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE PRODUCING OIL WELL-FILING ONE ORIGINAL & ONE COPY LONKER C #2

Compt. _____

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5171 EXPIRATION DATE 6/30/83

OPERATOR TXO PROD. CORP. API NO. 15-007-21,547-00-00

ADDRESS 200 W. Douglas, Ste. 300 COUNTY Barber

Wichita, KS 67202 FIELD Bloom

** CONTACT PERSON Harold R. Trapp PROD. FORMATION Simpson

PHONE 265-9441

PURCHASER Getty Trading & Transportation Co. LEASE Lonker

ADDRESS One Williams Center, Ste. 2424 WELL NO. C #2

Tulsa, OK 74172 WELL LOCATION 100' So C NW NW

DRILLING FWA, Rig #32 430 Ft. from NORTH Line and

CONTRACTOR P.O. Box 970 330 Ft. from WEST Line of

ADDRESS Yukon, OK 73099 the NW (Qtr.) SEC 22 TWP 32S RGE 12 (W)

PLUGGING Producer-never plugged WELL PLAT (Office Use Only)

CONTRACTOR See above

ADDRESS

TOTAL DEPTH 4870 PBTD 4846

SPUD DATE 12-28-82 DATE COMPLETED 1-28-83

ELEV: GR 1571 DF N/A KB 1582

DRILLED WITH (CANYE) (ROTARY) XXAXXX TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE Hauled

Amount of surface pipe set and cemented 8-5/8" @ 413' DV Tool Used? no

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.


A F F I D A V I T

Harold R. Trapp, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Handwritten signature of Harold R. Trapp

SUBSCRIBED AND SWORN TO BEFORE ME this 8th day of February, 19 83.



Handwritten signature of Bonnie J. Holcomb (NOTARY PUBLIC)

MY COMMISSION EXPIRES: 12-23-85

RECEIVED STATE CORPORATION COMMISSION FEB 9 1983 UNDERGROUND DIVISION Wichita, Kansas

** The person who can be reached by phone regarding any questions concerning this information.

SIDE TWO

OPERATOR TXO PRODUCTION CORP.

LEASE Lonker

ACO-1 WELL HISTORY ~~XXX~~
SEC. 22 TWP. 32S RGE. 12 (W)

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. C #2

FORMATION DESCRIPTION, CONTENTS, ETC.			TOP	BOTTOM	NAME	DEPTH
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.					SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Check if no Drill Stem Tests Run. DST #1, 4730-94' (Simpson), w/results as follows: IFP/30": 199-281#, strong blow ISIP/60": 851# FFP/45": 234-328#, GTS in 20", ga 9.7 incr. to 13.9 MCFD FSIP/90": 828# Rec: 45' SO&GCM + 60' HO&GCM + 855' free oil RAN O.H. LOGS					LOG TOPS Herington Onaga Wabaunsee Topeka Heebner Douglas Lans. Hertha Miss. Kinderhook Viola Simpson RTD LTD PBD	1874 -292 2698 -1116 2744 -1162 3145 -1563 3652 -2070 3686 -2104 3828 -2246 4244 -2662 4386 -2804 4540 -2958 4646 -3062 4770 -3188 4870 4861 4846
If additional space is needed use Page 2, Side 2						

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (X) (X) (X)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8"	24#	413'		100 300	common lime
Production		4-1/2"	10.5#	4860'		150	Class A .75 CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	4 JSPF	Simpson	4770-76

TUBING RECORD

Size	Setting depth	Packer set
2-3/8"	4808	4792

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Dumped 250 gals acetic acid + 1 bbl 2% KCl w/	
Treat w/500 gals 7% MSR acid	4770-76
Treated w/750 gals Clean-Sweep #2	"
Acidized w/1000 gals 7 1/2% HCl w/additives	"

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
2-7-83	pumping	N/A

Estimated Production -E.P.	Oil	Gas	Water	Gas-oil ratio
	36.74 BO bbls.	N/A	N/A % 3 BW bbls.	N/A

Disposition of gas (vented, used on lease or sold)	Perforations
sold	4770-76

San Oilwell Cementing
A Division of BJ Hughes, Inc.

P. O. Box 169
GREAT BEND, KANSAS 67530

CEMENTING TICKET No. 12873
and Invoice Number

12-29 12-29

Date: 12-28-82
Customer Order No.:
Sec: 22
Type: 32S
Range: 12W
Truck Called Out: 9:00 PM
On Location: 11:30 PM
Job Setup: 5:30
Job Completion: 6:00

Contractor: T.X.O.
City: F.W.A #32
Charge To: T.X.O.

Well No. and Perm: London C #2
Old 6 up Kill Rd 1/2's Barber Kansas

Depth of Well: 417
Depth of Job: 402
Size of Hole: 12 1/8
Ann. and Ch. of Cement: 900
Cement Left in casing by: 20

Kind of Job: Surface Casing
Conditions of Well at time of Cementing: Normal
Type of Plug: W/R Cup

Pressure Circulating: _____
Time Required Mixing Cement: _____
Milling Charge: _____
Pumping Cement: _____

Price Reference No. #2
Price of Job 411.82
Second Stage: _____
Sundry Truck: _____
Other Charges: _____
Pump Truck Mileage 7.50

Runs 10 1/2 to 9 5/8 to 402 ft. Cemented with 308K Red Weight 3% A-7 Filled with 100 lb Class A - 3% A-7 Displaced Plug to 387 ft with 2 1/2" Red Fresh Water.

Cement Did Cure!

Thanks

Cementor: Neal R
Helper: Randy D
Manned Left on Location: 878 Head + Mainfield
Medicine Lodge - Kansas
x by [Signature]

Prices Subject to Correction. Agent of Cementor or Operator

SALES TICKET FOR MATERIALS

QUANTITY SACS	BRAND AND TYPE	PRICE	TOTAL
300	Label weight (Class A)	4.30/sac	1290.00
100	Class A	5.00/sac	500.00
C.C. - A-7	1065	21/lb	232.65
AM. C.			
Oil	1-978 Wooden Rubber Cup		40.00
	Handling and Drums	9.20/lb	368.00
	Delivered by Truck No. T-42 & T-43 18-30	4.20/sac	62.22
	Delivered From Medicine Lodge		54.90
	Signature of Operator: <u>Boris C. J...</u>		2968.09