

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 33 Twp. 19 Rge. 16 (W)

Location as "NE/CNW%SW%" or footage from lines SW SE SW

Lease Owner Ben F. Brack Oil Co., Inc.

Lease Name Tammen Well No. 1

Office Address 310 Brown Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 19

Plugging completed December 26, 1959

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3770' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8 5/8" 1064' circulated with 500 sacks cement - 5 1/2" 3740' with 100 sacks cement behind.

Filled with sand to 3700', set 1/2 sacks cement with dump bailer, recovered? 2000' 5 1/2" - run tubing in hole to approx 700', circulated hole with heavy mud through 2" tubing (Gel Mud), displaced 20 sacks cement through 2" tubing at 420', heavy mud to 45', circulated hole full cement from 45' to 0' through 2" tubing.

Mudding and cementing by Halliburton Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1963

9-18-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clay Pipe Pulling Co.

Address Ellinwood, Kansas

STATE OF Kansas COUNTY OF Sedgewick, ss.

Ben F. Brack (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Ben F. Brack

(Address)


SUBSCRIBED AND SWORN to before me this 17th day of September, 1963

My commission expires

July 18, 1965

Madeline Kinsley
Notary Public.

K-165-00035-0000
 WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 503 East Merdock, Wichita, Kansas




Company: BEN F. BRACK OIL CO., INC.
 Farm: Tammen No. 1

SEC. 33 T. 19 R. 16W
 SW SE SW

Total Depth. 3753
 Comm. 4-9-53 Comp. 4-21-53
 Shot or Treated.
 Contractor.
 Issued. 7-18-53

County Rush

KANSAS



CASING:
 8 5/8 1064'
 5 1/2 3740'

Elevation. 2020 DF

Production. Flow 45 bbls.

Figures Indicate Bottom of Formations.

shale & clay	40
shale & shells	360
sand & shale	420
sand	575
shale & shells	925
red bed	1045
shale	1050
anhydrite	1085
shale & shells	1760
lime & shale	2100
sand	2175
shale & lime	2185
lime	2260
lime & shale	3415
lime	3753
Total Depth	

TOPS:	
Brown lime	3416
Lansing	3430
Arbuckle	3712

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 16 1964
 7-16-64
 CONSERVATION DIVISION
 Wichita, Kansas