

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rush County, Sec. 33 Twp. 19 Rge. 16 (E) (W)

Location as "NE/CNWxSWx" or footage from lines SW SW SE 1/4

Lease Owner Clarence J. MERMIS

Lease Name Tammen Well No. 2

Office Address Route No. 1

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed 4-12-66 19__

Application for plugging approved 4-13-66 19__

Plugging commenced 4-13-66 19__

Plugging completed 4-21-66 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3763 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1075	None
				5 1/2	None	2906

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1966
4-28-66

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed in feet to _____ feet for each plug set.

Moved in. Rigged up. Couldn't get slips out of head.

Tried to bail down hole - wouldn't bail. Mixed 6 sacks of cement.

Tried to bail down hole - wouldn't bail.

Shot pipe at 3000'. Shot pipe at 2900'.

Pulling pipe.

Build rock bridge. Capped well with 10 sacks of cement. Well completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of April, 19 66

My commission expires May 27, 1969

Notary Public.

BEN F. BRACK OIL COMPANY, INC.
309-10 BROWN BUILDING
WICHITA 2, KANSAS

TAMMEN #2

SW SW SE

Sec. 33-19S-16W
Rush County, Kansas
Commenced: 6-4-53
Completed: 6-18-53

TOTAL DEPTH: 3760'
ELEVATION: 2028' DF
2026' Gr.

WELL LOG

Surface Soil & Clay	0 -	126'
Shale, Shells, & Lime		385
Sandy Shale		440
Sand		600
Shale & Shells		720
Red Bed & Shells		1055
Red Bed & Shale		1068
Anhydrite		1100
Red Bed & Shells		1375
Shale & Shells		1780
Lime & Shale		2735
Shale & Lime		2980
Lime & Shale		3170
Shale & Lime		3235
Lime & Shale		3470
Lime		3554
Lime & Shale		3615
Lime		3720
Lime & Shale		3737
Lime		3760' T.D.

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1966
4-29-66
CONSERVATION DIVISION
WICHITA, KANSAS

The above depths denote bottom of formations.

CASING

8 5/8" 1075'
5 1/2" 3759'

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By Emil E. Bauer

WITNESSED:
Gertrude Cust

June 23, 1953.